

Introduction to Construction Quality Management

Introduction to Construction Quality Management (CQM)

1. What Is Construction Quality Management?

- **Definition** – A systematic process that ensures construction projects meet specified requirements for performance, durability, safety, and client expectations.
- **Goal** – Deliver a finished product that is fit for purpose, complies with codes/standards, and is completed within budget and schedule.

2. Core Elements of CQM

Element	Description	Key Activities
Quality Planning	Establishes the quality objectives, standards, and procedures before work begins.	• Develop a Quality Management Plan (QMP) • Identify applicable codes, specifications, and client requirements • Define inspection and testing protocols • Process audits
Quality Assurance (QA)	Preventive actions that build quality into processes.	• Training and competency verification • Supplier and subcontractor pre-qualification
Quality Control (QC)	Reactive actions that verify that deliverables meet the required standards.	• On-site inspections • Material testing • Non-conformance reporting and corrective actions
Continuous Improvement	Ongoing refinement of processes based on lessons learned.	• Post-project reviews • Root-cause analysis of defects • Updating the QMP and standard operating procedures

Introduction to Construction Quality

3. Quality Management Plan (QMP) – The Blueprint Management

1. Project Scope & Requirements

- List of design specifications, codes, client expectations.

2. Organizational Structure

- Roles: Quality Manager, QA/QC Inspectors, Site Superintendent, Subcontractor Quality Representatives.

3. Documentation Control

- Document register, revision tracking, distribution list.

4. Inspection & Test Plan (ITP)

- Sequence of inspections, responsible parties, acceptance criteria, hold points.

5. Materials & Equipment Management

- Approved suppliers, material certificates, storage & handling procedures.

6. Non-Conformance Management

- NCR (Non-Conformance Report) process, corrective action workflow, closure verification.

7. Reporting & Communication

- Daily QC logs, weekly quality meetings, progress dashboards.

8. Audit & Review Schedule

- Internal audits (monthly), external audits (as required), management review meetings.

4. Key Tools & Techniques

- **Checklists & Inspection Forms** – Standardize what is examined at each stage.
- **Control Charts** – Monitor process stability (e.g., concrete slump, weld bead size).

Introduction to Construction Quality Management

- **Six Sigma / Lean Principles** – Reduce variation and eliminate waste.
 - **BIM-Based Quality Management** – Link model data to inspection points and as-built verification.
 - **Digital QC Platforms** – Mobile apps for real-time data capture, photo documentation, and NCR tracking.
-

5. Common Quality Issues & Mitigation Strategies

Issue	Typical Cause	Mitigation
Concrete Cracking	Poor mix design, inadequate curing	Pre-mix approval, temperature-controlled curing, proper formwork design
Dimensional Deviations	Inaccurate layout, lack of reference points	Use laser positioning, verify layout before critical work, maintain as-built drawings
Material Substitution	Cost pressure, supplier change	Strict material approval process, material certificates, on-site verification
Welding Defects	Inadequate welder qualification, improper parameters	Welding procedure specification (WPS) compliance